

Proposal

Run: 9fea19c3-53a9-4e4a-8d59-cd6e3af09d7b

Summary

This proposal covers the installation of forty Cat6A network drops in an office building in Sacramento, CA, including all materials and labor. The total cost is \$8,159.89, comprising \$2,338.00 in materials, \$5,200.00 in labor, and \$621.89 in tax. The estimate includes assumptions for label sheets and excludes costs for patch panel housing and equipment rack due to lack of pricing evidence. The project will be performed by an electrician and an apprentice, with labor hours totaling 60 and 20 respectively.

Terms

Payment terms are net 30 days from invoice date. The proposal is valid for 30 days from the date of issuance. Any changes to scope will be addressed through a change order. Work will be performed during normal business hours, Monday through Friday.

Valid until: 2025-12-01

Bill of Materials

Item	Qty	Unit Cost	Ext	Note
Cat6A plenum cable, 1000 ft box	2	189.00	378.00	[1]
Cat6A keystone jack	40	8.50	340.00	[2]
1-port wall plate	40	3.25	130.00	[3]
Patch panel port	40	4.75	190.00	[4]
Cable management ring	40	2.10	84.00	[5]
Velcro cable tie, 100-pack	4	12.00	48.00	[6]
Wall mount bracket	40	6.40	256.00	[7]
RJ45 connector, 50-pack	2	18.00	36.00	[8]
Surface raceway, 10 ft	80	9.80	784.00	[9]
J-hook, 25-pack	2	22.00	44.00	[10]
Firestop putty, 5 lb	1	34.00	34.00	[11]
Label sheet, 100 labels	2	7.00	14.00	assumption
Patch panel housing	1	0.00	0.00	assumption
Equipment rack	1	0.00	0.00	assumption

Labor

Role	Hours	Rate Key	Cost	Note
------	-------	----------	------	------

electrician

electrician

[12]

apprentice

20

apprentice

-

[13]

Assump tions

- Label
sheet,
100
labels:
Code
requires
labels on
both ends
of every
cable (80
labels for
40
drops), so
2 sheets
are
needed;
evidence
only lists
1 sheet
for 40
drops.
- Patch
panel
housing:
No
pricing
evidence
found for
patch
panel
housing;
cost not
included.
- Equipme
nt rack:
No
pricing
evidence
found for e
quipment
rack; cost
not
included.

Code

Claims

- Plenum-rated Cat6A cable is required for installations in air-handling spaces.
- Penetrations of fire-rated assemblies must be firestopped with approved methods.
- Labels are required on both ends of every cable.

Totals

Materials:
2338.00
Labor:
5200.00
Tax:
621.89
Total:
8159.89

Citations

1. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Cat6A plenum cable, 1000 ft box: \$189.00 per box. Need 2 boxes for 40 drops.
2. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Cat6A keystone jack: \$8.50 each. Need 40 jacks for 40 drops.
3. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] 1-port wall plate: \$3.25 each. Need 40 plates for 40 drops.
4. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Patch panel port: \$4.75 each. Need 40 ports for 40 drops.
5. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Cable management ring: \$2.10 each. Need 40 rings for 40 drops.
6. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Velcro cable tie, 100-pack: \$12.00 per pack. Need 4 packs for 40 drops.
7. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Wall mount bracket: \$6.40 each. Need 40 brackets for 40 drops.
8. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] RJ45 connector, 50-pack: \$18.00 per pack. Need 2 packs for 40 drops.
9. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Surface raceway, 10 ft: \$9.80 each. Need 80 pieces for 40 drops.
10. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] J-hook, 25-pack: \$22.00 per pack. Need 2 packs for 40 drops.
11. [bf1abcd4-75c7-4ef7-bfcf-a23e1d7651c5] Firestop putty, 5 lb: \$34.00 each. Need 1 tub for 40 drops.
12. [15db33bd-a501-473d-aa0b-76c100cc5cff] Electrician: 1.5 hours per drop at \$75.00 per hour.
13. [15db33bd-a501-473d-aa0b-76c100cc5cff] Apprentice: 0.5 hours per drop at \$35.00 per hour.